



NOTES

	details
	All dimensions are in millimetres unless noted otherwise and are to be checked by the contractor prior to construction.
2.	Work to be carried out in accordance with: <ul style="list-style-type: none"> • DCC Good Practice Guide BM4 - Mortar for Masonry in Devcon • DCC Good Practice Guide BM6 - Vegetation Removal • PPG5 Pollution Prevention Guidelines
3.	Drilling to be read in conjunction with: DCCP22381-EDG-SRWV-KENTON-DR-S-002-RevP0-Site Plan and Access Route
4.	Temporary pipe in watercourse to be removed to Lemonford Depot.
5.	Garden fences to be removed and replaced as agreed with Parish and landowner.
6.	Channels to be laid straight, Fig. 6.
7.	Fall 1:123 between chainage 0 and 88 m.
8.	Bed to be recharged, filling in areas of scour identified during survey.
9.	Excess voids from storm damage to be filled with C32/40 concrete.
10.	Timber baffles to be sweet chestnut, fixed using a suitable epoxy resin approved by DCC engineer.

PRELIMINARY
ISSUE

Rev	Date	Des	Drawn	Revisions	Chk
P0	05/06/24	O.C.	O.C.	Preliminary Issue	T.M.
P1	27/06/24	O.C.	O.C.	Concrete specification changed	T.M.
P2	08/07/24	O.C.	O.C.	Baffles and associated notes added.	T.M.



Engineering Design Group

Crow Tor	Tel 0845 155 1004
Great Moor House	Fax 01392 382342
Bittern Road	
Exeter	customer@devon.gov.uk
EX2 7NL	www.devon.gov.uk

DB

EWRC KENTON FLOOD IMPROVEMENT - FOOTPATHS

DRAWING TITLE

PROPOSED GENERAL ARRANGEMENT

Drawing Number

DCCP22381 - EDG - SRW
KENTON - DR - S - 003

AS SHOWN	Size A1	Revision P2
----------	------------	----------------